

# Milestone Recap

---

Kickoff with staff	Late May
Study Team   Prioritization Criteria	Late May
Development of Draft Memo	Early June
Policy Committee   Draft Memo Approval	Mid June
Refinement of Memo	Early July
Study Team and Policy Committee Workshops	Mid July
Study Team   Vetting of Improvement Types	Late July

# Workshop Outcomes

---

- Add US 221 to the Access Management Projects
- Changes to Capacity Improvement Projects:
  - Bump up New Cut Road to Tier 1 based on crash score
  - Add and score Bishop Road and Floyd Road
- Provide planning-level cost for:
  - 1 In-Process Project
  - Access Management Projects
  - Tier 1 Capacity Improvement Projects
- Provide planning-level per-mile cost for New Connection Projects

# Tier 1 Improvement Types

Corridor	From	To	Current Typical Cross Section	Proposed Typical Cross Section
Berry Shoals Rd	SC 101	SC 290	Two lanes (24')	A
SC 357	US 29	SC 358	Two lanes (24')	A
Valley Falls Rd	SC 9	US 176	Two lanes (22')	B
Cannons Campground Rd/ Gossett Rd	I-85	Drayton Rd	Two lanes (20' to 28')	A
Old Furnace Rd	US 176	US 221	Two lanes (22' to 24')	B
Highway 292	US 29	SC 9	Two lanes (22' to 26')	A
Highway 296 (SW Spartanburg County)	SC 290	SC 146	Two lanes (20' to 26'); targeted three lanes (40')	C
New Cut Road	Asheville Highway	SC 292	Two lanes (20' to 24'); targeted three lanes (40')	A

## Proposed Typical Cross Sections

A = Two lanes (24' w/2' paved shoulders); targeted three lanes (36' w/2' paved shoulders); targeted intersection improvements

B = Two lanes (24' w/2' paved shoulders); targeted turn lanes; targeted intersection improvements

C = Two lanes (24' w/2' paved shoulders); targeted three lanes (36' w/2' paved shoulders); targeted multimodal improvements; targeted intersection improvements

# Template Scopes of Work



CORRIDOR	PROJECT TYPE
SC 9	Access management
Asheville Highway	Right-of-way reallocation; multimodal improvements; gateway beautification
Berry Shoals Road	Capacity; safety; intersection improvements
Highway 292	Context-sensitive design

# Next Steps

---

Cost Estimates and Final Memo

Early August

Policy Committee | Final Memo Approval

August 8<sup>th</sup>

Template Scopes of Work

Early September